

www.lcra.org

HIGHLAND LAKES WATERSHED ORDINANCE

WATER QUALITY MANAGEMENT TECHNICAL MANUAL

Effective July 1, 2007

HIGHLAND LAKES WATERSHED ORDINANCE

WATER QUALITY MANAGEMENT TECHNICAL MANUAL

EFFECTIVE JULY 1, 2007

FIFTH EDITION

Lower Colorado River Authority

TABLE OF CONTENTS

DESIGN SPREADHEET MODEL	FRONT POCKET
STORMWATER CREDITS FOR INVIDIDUAL LOTS MODEL	FRONT POCKET
TEXAS HILL COUNTRY LANDSCAPE OPTION	FRONT POCKET
DREDGE AND FILL STANDARDS HANDBOOK	FRONT POCKET
HIGHLAND LAKES WATERSHED ORDINANCE HANDBOOK	

SECTION I – DEVELOPMENT

CHAPTER 1 PERMIT REQUIREMENTS AND PROCEDURES

			Page
1.1	INT	RODUCTION	1-1
1.2	Ex	EMPTIONS	
1.3	WF	RITTEN NOTIFICATION REQUIRED	
1.4	DE	VELOPMENT PERMIT	1-4
	1.4.1	Overview	1-4
	1.4.2	Permit Process Flow Chart	1-5
	1.4.3	Development Permit Application Procedures	1-6
	1.4.4	Permit Amendment	1-8
	1.4.5	Pre-development/ Concept Plan Meeting Procedures	1-8
	1.4.6	Financial Security for Erosion & Sedimentation Controls	1-8
	1.4.7	Notice of Application for Development Permits	1-9
	1.4.8	Comments	1-9
	1.4.9	Public Meetings	1-9
	1.4.10	Master Plan	1-9
	1.4.11	Variances	1-9
	1.4.12	Appeals	1-10
1.5	BM	IP MAINTENANCE PERMIT	1-10
	1.5.1	Overview	1-10
	1.5.2	Procedures	1-10
1.6	GE	NERAL UTILITY PERMIT	1-11
	1.6.1	Overview	1-11
	1.6.2	Procedures	1-11
1.7	Pri	ELIMINARY AND FINAL PLAT REVIEW	1-12
	1.7.1	Overview	1-12
	1.7.2	Procedures	1-12

CHAPTER 2 MEETING WATER QUALITY MANAGEMENT PERFORMANCE STANDARDS

2.1	IN	TRODUCTION	2-1
2.2	PF	RE DEVELOPMENT PLANNING	2-2
2.3	W	ATER QUALITY MANAGEMENT (BMP DESIGN AND ASSESSMENT)	2-2
		Alternate Standards	
	2.3.2	Stormwater Credits	2-4

	2.3.3	Water Quality BMP Sizing	
2.4	BU	FFER ZONES	
	2.4.1	Buffer Zone Technical Requirements	
2.5		INSTRUCTION- PHASE EROSION AND SEDIMENT CONTROL	
2.6	W	ATER QUALITY EDUCATION	

CHAPTER 3 EROSION AND SEDIMENT CONTROL BEST MANAGEMENT PRACTICES

3.1	INT	RODUCTION
3.2	Ere	OSION CONTROL BMPS
	3.2.1	Interceptor Swale
	3.2.2	Diversion Dikes
	3.2.3	Pipe Slope Drain
	3.2.4	Channel Stabilization
	3.2.5	Outlet Stabilization
	3.2.6	Level Spreaders
	3.2.7	Subsurface Drains
	3.2.8	<i>Vegetation</i>
	3.2.9	Irrigation
	3.2.10	Cedar Mulch
	3.2.11	Blankets and Matting
	3.2.12	Organic Compost Mulch
	3.2.13	Hydraulic Mulch
	3.2.14	Sod
	3.2.15	Dust Control
3.3	Sei	DIMENT CONTROL BMPS
	3.3.1	General Guidelines
	3.3.2	Temporary Construction Entrance/Exit
	3.3.3	<i>Silt Fence</i>
	3.3.4	Triangular Sediment Filter Dikes
	3.3.5	<i>Rock Berms</i>
	3.3.6	High Service Rock Berms
	3.3.7	Brush Berms
	3.3.8	<i>Check Dams</i>
	3.3.9	Vegetative Buffers
	3.3.10	Inlet Protection
	3.3.11	Stone Outlet Sediment Trap
	3.3.12	Sediment Basins
	3.3.13	Fiber Rolls
	3.3.14	Dewatering Operations
	3.3.15	Spill Prevention and Control
	3.3.16	Creek Crossings
	3.3.17	Concrete Washout Areas

CHAPTER 4 PERMANENT STRUCTURAL BEST MANAGEMENT PRACTICES (WATER QUALITY TREATMENT)

4.1	In	TRODUCTION	4-1
4.2	\mathbf{W}	ATER QUALITY TREATMENT BMP GUIDELINES	
	4.2.1	General Deisgn Guidelines	
	4.2.2	Bioretention Basin	
	4.2.3	Extended Detention Basin	4-11
	4.2.4	Sand Filter Basin	4-15
	4.2.5	Wet Basins	4-21
	4.2.6	Retention/Irrigation	
	4.2.7	Vegetative Filter Strips	
	4.2.8	Stormater Infiltration Devices	4-46
4.3	St	ORMWATER CREDITS	4-53
	4.3.1	Porous Pavement/ Pervious Pavers Credit	
	4.3.2	Rainwater Harvesting/ Cistern Credit	4-59
	4.3.3	Soil Amendment and Conservation Landscaping Credit	
	4.3.4	Disconnection of Rooftop Runoff Credit	
	4.3.5	Natural Area Preservation Credit	
	4.3.6	Wet Vault Credit	4-76
	4.3.7	Dealing with Multiple Credits	
4.4	St	ORMWATER MANAGEMENT FOR INDIVIDUAL LOTS	
4.5		ORMWATER MANAGEMENT FOR RIDGELINE/ISOLATED LOTS	

CHAPTER 5 PERMANENT BMP MAINTENANCE GUIDELINES

5.1	Μ	AINTENANCE PLAN	
5.2	Gi	ENERAL GUIDELINES	
5.3	BA	SIN DE-WATERING	
5.4		DIMENT DISPOSAL	
5.5		MP MAINTENANCE REQUIREMENTS	
	5.5.1	Detailed Inspections and General Maintenance	
	5.5.2	General Site Maintenance	
	5.5.3	Inspection and Maintenance of Water Quality Basin BMPs	5-5
5.6	BN	AP MAINTENANCE PERMIT	

CHAPTER 6 DREDGE AND FILL STANDARDS

6.1	PI	REFACE	
6.2	D	EFINITIONS	6-2
6.3	D	REDGE AND FILL ACTIVITIES	
6.4	0	THER REGULATIONS	
6.5	H	IGHLAND LAKES ELEVATION LEVELS	6-4
6.6		ROPERTY OWNERSHIP	
	6.6.1	Privately Owned Land	
		Publicly Owned Land	

6.7	LAND RECLAMATION	6-5
6.8	WATER QUALITY PROTECTION	6-5
6.9	ENSURING NAVIGABILITY OF WATERS	6-6
6.10	SHORELINE PROTECTION TECHNIQUES	6-6
	5.10.1 Use of retaining walls and riprap to stabilize eroded shorelines	6-8
6.11	ENFORCEMENT OF DREDGE AND FILL STANDARDS	6-12
6.12	U.S. ARMY CORPS OF ENGINEERS REQUIREMENTS	6-12
6.13	LAKEWIDE PERMIT	6-13

SECTION II – QUARRY AND MINE ACTIVITY

CHAPTER 1 PERMIT REQUIREMENTS AND PROCEDURES

1.1	INTRODUCTION	
1.2	EXEMPTIONS	
1.3	WRITTEN NOTIFICATION REQUIRED	
1.4	QUARRY/MINE CERTIFICATION	
1.5	QUARRY/MINE PERMIT	
	e	

CHAPTER 2 MEETING WATER QUALITY MANAGEMENT PERFORMANCE STANDARDS

2.1	In	TRODUCTION	
2.2	Pr	RE QUARRY/MINE PLANNING	
2.3		ATER QUALITY MANAGEMENT	
	2.3.1	Stormwater from Project Area Not Draining to Pit	
	2.3.2	Stormwater from Project Area Draining to Pit	
	2.3.3	Other Local State and Federal Regulations	
	2.3.4	Potential Submittals to LCRA	
	2.3.5	Groundwater Quality Protection	
2.4	Βι	JFFER ZONES	
	2.4.1	Buffer Zone Technical Requirements	
2.5	EF	ROSION AND SEDIMENT CONTROL	
2.6		EPORTING	
GL	OSSAR	Y	G-1
BIB	LIOGR	АРНУ	B-1

APPENDIX

1.1	LCRA HIGHLAND LAKES WATERSHED ORDINANCE	
	1.1.1 Ordinance Watershed Map	
1.2	DEVELOPMENT AND QUARRY/MINE PERMIT APPLICATION FORM	
1.3	FEE SCHEDULE	

- 1.4 "NOTIFICATION OF NO PERMIT REQUIRED" FORM
 - 1.4.1 Dredge and Fill Standards Checklist
- 1.5 DEVELOPMENT PERMIT SUBMITTAL REQUIREMENTS
 - 1.5.1 Administrative Completeness Checklist
- 1.6 MASTER PLAN SUBMITTAL REQUIREMENTS
- 1.7 BMP MAINTENANCE PERMIT SUBMITTAL REQUIREMENTS
 - 1.7.1 BMP Maintenance Permit Application
 - 1.7.2 Permanent BMP Inspection Checklist Example- Water Quality Basin
 - 1.7.3 Permanent BMP Inspection Checklist Example- Vegetative
- 1.8 UTILITY GENERAL PERMIT SUBMITTAL REQUIREMENTS
- 1.9 PRELIMINARY PLAN SUBMITTAL REQUIREMENTS
- 1.10 FINAL PLAT SUBMITTAL REQUIREMENTS
- 1.11 PLAT NOTES
- **1.12** LETTER OF CREDIT EXAMPLE FORMS
- **1.13** NEWSPAPER NOTICE EXAMPLE
- **1.14 PROJECT SIGN NOTICE**
 - 1.14.1 Mailed Notice Example- Development Permit
 - 1.14.2 Mailed Notice Example- Master Plan
- 1.15 INSPECTION PROCEDURES
- 1.16 PRE-CONSTRUCTION MEETING HANDOUT- RESPONSIBLE PARTY DESIGNATION
- 2.1 EXAMPLE ALTERNATE DEVELOPMENT STANDARDS- SINGLE FAMILY DEVELOPMENT
 - 2.1.1 1/5th acre lot using stormwater credits to gain alternate standards compliance
 - 2.1.2 ¹/₂ acre lot using stormwater credits to gain alternate standards compliance
- 2.2 EXAMPLE BMP DESIGN- SINGLE FAMILY SUBDIVISION PROJECT
- 2.3 EXAMPLE BMP DESIGN- LARGE COMMERCIAL DEVELOPMENT PROJECT
- 2.4 HYDROLOGY AND HYDRAULICS REFERENCE TABLES
- 2.5 PRE DEVELOPMENT PLANNING
- 2.6 **BUFFER ZONES**
- 2.7 CONSTRUCTION-PHASE EROSION AND SEDIMENT CONTROL
 - 2.7.1 Erosion and Sediment Control Handouts (See <u>www.lcra.org</u> for Spanish version)
 - 2.7.2 Erosion and Sediment Control General Notes
 - 2.7.3 Notes for Construction in Creeks
- 2.8 SITE CHARACTERISTICS FOR HIGH EROSION POTENTIAL
- 2.9 WATER QUALITY EDUCATION
- 2.10 INDIVIDUAL LOT BEST MANAGEMENT PRACTICE DETAILS
 - 2.10.1 Porous Pavement and Pavers
 - 2.10.2 Rain Garden
 - 2.10.3 Dry Well
 - 2.10.4 Conservation and Landscape Guidelines

TABLES

SECTION 1 – DEVELOPMENT

1-1	SUMMARY OF PROJECT REQUIREMENTS	1-2
2-1	SUMMARY OF PERFORMANCE STANDARDS	2-1

4.3.2 Rainwater Harvesting/Cistern Credit

Definition of Rainwater Harvesting/Cistern Credit


A credit is given when rainwater collection systems are used to retain roof runoff resulting in the reduction of the development impervious cover. Rainwater collection systems will generate an impervious cover reduction for the area that drains to the rainwater collection barrel(s) based on the ratio of the barrel volume to the roof (catchment) area. Rainwater collection can occur at single family residences, multi-family complexes, and commercial developments. This credit can be used to gain compliance with the Alternate Standards or reduce the water quality volume. The maximum impervious cover reduction is 75% to account for rainwater system maintenance and operation challenges that may occur over the system life.

Rainwater collection can also be used to satisfy the roof-top disconnection credit, but can not be counted as a credit for both rainwater harvesting and roof-top disconnection.

Reduced impervious cover credit is computed per the following equation and figure:

 $A_r = A_{RT} * %_{IC \ REDUCTION \ FACTOR}$ (per Figure below)Where: $A_r =$ Allowable reduction in impervious cover $A_{RT} =$ Area of roof-top directed to rain barrel(s) (catchment area) (sq ft) $\%_{IC \ REDUCTION \ FACTOR} = \%$ Impervious area reductionRBV = Rain barrel volume (cubic feet)

Rainwater Harvesting Effectiveness



Rainwater Collection Credit

Restrictions on the Credit

The rainwater harvesting credit is subject to the following restrictions:

- Rainwater collection and distribution systems must be designed and installed per the requirements in this Section;
- A rainwater collection system maintenance plan must be approved by LCRA before issuance of a development permit. The maintenance plan will need to identify the responsible maintenance party and allow for periodic LCRA inspection;
- The development permit will include a condition that the contractor must contact LCRA 48 hours prior to the final completion of the rainwater collection system;
- Storage shall be provided in cisterns, rain barrels, tanks, or other approved methods.
- Overflows from rainwater tanks should be diverted to grassy swales and/or lawns to promote infiltration of excess runoff volume.

Example calculation, the required water quality volume before the credit for a ten (10) acre site with 30 single family lots would be:

Impervious cover = 3 acres = 30%1-year runoff volume = 0.59 inches based on Equation 2.9 Water quality volume = (0.59 inches) * (10 acres) * (43,560/12) = 21,417 cubic- feet. Applying the credit, each single family lot will utilize a rainwater collection system per the criteria. Each house has a roof area of 2,000 square feet, however, individual roof design is not known at this phase, thus a factor of 0.75 is applied to the roof area, resulting in the assumption that 1,500 square feet can be drained to rainwater collection tanks. The home storage barrel(s) will provide 1,500 gallons of storage.

Roof area draining to collection barrels = 2,000 square feet * 0.75 = 1,500 square feet Barrel volume = 1,500 gallons per plat note and deed restriction = 200 cubic feet Barrel volume to catchment area = 200 / 1,500 = 0.13Using the Rainwater Harvesting Effectiveness Figure, % IC Reduction = 43% A_r = Allowable impervious cover reduction per house = $(1,500) \times (0.43) = 645$ square feet Impervious cover with credit = (3 acres) - ((30 lots) * (645 sq. ft)) = 2.56 acresEffective impervious cover = 26%1-year runoff volume = 0.52 inches based on Equation 2.9 Water quality volume = (0.52 inches) * (10 acres) * (43,560/12) = 18,876 cubic-feet.

The BMP water quality volume is reduced by 12% in this example.

Description

Rainwater harvesting is a method of diverting and collecting rainfall that falls onto impervious surfaces, such as roofs. Harvested rainfall is typically used for indoor residential use, landscape irrigation, or both. By capturing and slowly releasing rooftop runoff over vegetated areas, rainwater harvesting can reduce stormwater volume and flow rates and the resultant erosion and pollutant discharges to surface waters. Schematics of a complex rainwater harvesting system are presented in Figures 4.21 and 4.22 below.


Application


In a rooftop rainwater harvesting system, runoff flows via gravity through gutters and downspouts into a storage tank where it is slowly released to landscaped areas or stored for later use. Rainwater harvesting systems are primarily designed for conservation—long-term storage and use—rather than to mitigate the impacts of impervious cover and increased runoff. If a tank is full or near-full (beneficial for conservation and long-term use) it will not provide stormwater benefits.

Rainwater harvesting systems can provide pretreatment for other BMPs and qualify for stormwater credit to reduce water quality basin size or gain compliance with the Alternate Standards. The collection systems are equally appropriate in large-scale landscapes, such as parks, schools, commercial sites, parking lots and apartment complexes and in small residential landscapes. Rainwater harvesting is a feasible alternative for intensively developed areas and is suitable for steep terrain and flat landscapes where collected water can be diverted to depressed landscaped areas or grassy swales.

Rooftop rainwater harvesting provides a lower-cost method of treating surface water runoff than other permanent water quality treatment structures. Costs include the storage tank, filtering system, and pressure pump. Routine maintenance is a minor expense but is essential for the system to properly function. In an effort to encourage water conservation, the State provides financial incentives and tax exemptions to offset the equipment costs. Municipal incentives are also available in some areas.

Additional information can be found in the Texas Rainwater Harvesting Manual.





Design Guidelines

Rainwater Harvesting is a system of collecting, conveying, and storing rainfall from impervious surfaces and directing water to where it is needed.

- (1) *Catchment surface*: The collection surface is the "footprint" of the roof. The effective collection surface is the length times the width of the roof from eave to eave and front to rear.
- (2) *Conveyance systems*: Gutters should be properly sized and located to maximize catchment efficiency and prevent overrunning. Overrunning can result from an inadequate number of downspouts, excessively long roof distances from ridge to eave, steep roof slopes, and inadequate gutter maintenance. Preventative strategies may include modifications to the size and configuration of gutters and addition of gutter boxes with downspouts and roof diverters near the eave edge. Gutters should slope towards the downspout with the outside face of the gutter lower than the inside face to encourage drainage away from the building wall. Downspouts should provide 1 square inch of downspout opening for every 100 square feet of roof area. The first flush runoff should outfall onto an adequately sized rock splash pad that will prevent erosion, channeling, or puddling.




Figure 4.21: Complex water harvesting system with roof catchment, gutter, downspout and storage tank. (City of Austin Energy's Green Building Fact Sheet, 1995)

(3) *Storage*:

i. *Filtration*: Leaf screens, first-flush diverters, and roof washers should be installed on inflow lines to prevent trash and organics from entering the storage area. Permanent openings must be screened to prevent insect infestation in the piping and standpipe.




Figure 4.22: Standpipe first flush diverter. The recommended diversion of first flush ranges from one to two gallons of first-flush diversion for each 100 square feet of collection area. (TWDB, 2005)




Figure 4.23: Standpipe with ball valve. The standpipe with ball valve is a variation of the standpipe filter. As the chamber fills, the ball floats up and seals on the seat, trapping first-flush water and routing the balance of the water to the tank. (TWDB, 2005)




Figure 4.24: Box roof washer. Roof washers are recommended for drip irrigation systems. (TWDB, 2005)

- (4) *Delivery system*: The distribution directs water to plants from storage tanks to garden hoses, constructed (non-erosive) channels, or manual drip systems. Drip and other types of integrated distribution systems may require a small pressure pump to distribute the water. If a drip irrigation system is not used, the water can gravity-flow to garden hoses. In addition, the water can be delivered to the house for domestic use.
- (5) *Stormwater Credits*: Stormwater credit is given when rooftop runoff is collected, stored per the volume requirements, and discharged through everyday consumption. The figure above illustrates the percentage of impervious cover reduction that can be obtained using the above listed criteria. The percentage of impervious cover reduction is based upon the percentage of rooftop runoff that is captured. A maximum reduction of 75% of the rooftop impervious cover will be given. Credit is documented at the concept plan stage. Criteria for the rainwater harvesting system must be included in the deed restrictions to be eligible for the stormwater credit.
- (6) *System Maintenance*: The system should be checked annually and after every rainfall to insure the system is operating optimally. The following maintenance should be conducted:
 - Keep debris out of holding areas;
 - Remove collected debris from the first-flush diversion standpipe after each rainfall event;
 - Control and prevent erosion; block and repair erosion trails;
 - Keep debris out of gutters and downspouts;
 - Control and prevent erosion; block and repair erosion trails;
 - Flush debris from storage container bottoms;

- Clean and maintain filters, especially those on drip irrigation systems;
- Expand watering basins as plants grow; and
- Roof washers must be readily accessible for regular maintenance.

4.3.3 Soil Amendment and Conservation Landscaping Credit

Definition of Soil Amendment and Conservation Landscaping Credits

A credit is given when lawns and landscape areas within the development utilize the Soil Amendment or Conservation Landscaping guidance in this section. The benefit of these designs over more traditional lawns is the placement of sufficient soil depth and appropriate vegetation that promotes infiltration and less stormwater runoff.

The Soil Amendment Credit relies on native soils, appropriate soil depths, and low maintenance turf grasses to reduce the runoff volume. The stormwater credit for Soil Amendment is the reduction of project impervious cover by 2%.

The Conservation Landscaping Credit is based upon planting a reduced turf area and incorporating native plants, shrubs, trees and perennials to retain stormwater on site and require minimal chemicals to sustain a native and colorful landscape. The stormwater credit for Conservation Landscaping is the reduction of impervious cover by 5%.

These credits can be used to gain compliance with the Alternate Standards or reduce the water quality volume.

Soil Amendment Credit

$A_r = A_D * 0.02$

Where: $A_r =$ Allowable reduction in impervious cover $A_D =$ Area of development

Restrictions on the Credit

The soil amendment credit is subject to the following restrictions:

- Home-builders coordinate with LCRA during soil placement. This coordination will be identified as a permit condition and will allow LCRA to inspect the soil depth and quality prior to grass placement.
- The soil amendment requirement shall be noted on the plat and included in the development deed restrictions.

Example calculation, the required water quality volume before the credit for a ten (10) acre site with 30 single family lots would be:

Impervious cover = 3 acres = 30% 1-year runoff volume = 0.59 inches based on Equation 2.9